


15-119-10170-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

### WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Meade County. Sec. 35 Twp. 32S Rge. 27 (E) (W)  
Location as "NE/CNWSW" or footage from lines 1250' fr. south, 1650' fr. west  
Lease Owner The Shamrock Oil and Gas Corporation  
Lease Name P. G. Reimer "A" Well No. 1  
Office Address Box 631, Amarillo, Texas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry  
Date well completed 4-21 19 60  
Application for plugging filed 4-21 19 60  
Application for plugging approved 4-21 19 60  
Plugging commenced 4-21 19 60  
Plugging completed 4-21 19 60  
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production None 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Frank Broadfoot, St. John's, Kansas  
Producing formation None Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 5,772 Feet  
Show depth and thickness of all water, oil and gas formations.

#### OIL, GAS OR WATER RECORDS

#### CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
None				9 5/8"	1,541'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.  
Filled hole with heavy mud to 1,500'. Pushed 9 5/8" cementing plug to 1,500'. Spotted 25 sacks with drill pipe. Filled hole with mud to 700'. Pushed 9 5/8" plug to 700'. Spotted 25 sacks cement. Filled hole to 35' with mud and set 9 5/8" plug. Spotted 15 sacks cement to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
APR 27 1960  
4-27-60  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Halliburton Oil Well Cementing Company  
Address Liberal, Kansas

STATE OF Texas COUNTY OF Potter ss.  
T. S. Clopton (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T. S. Clopton

Box 631, Amarillo, Texas  
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of April, 19 60

Pauline Powell  
Notary Public  
Potter County, Texas

My commission expires 6-1-61

15-119-10170-00-00

Shamrock Oil & Gas

C SW

P. C. REIMER "A" NO. 1

Section 35, Township 32 South, Range 27 West  
Meade County, Kansas

9 5/8 - 15 4/1

*dy*

0' - 170'	Sand, shale, & shells
170' - 825'	Red beds
825' - 2,230'	Shale & shells
2,230' - 3,102'	shale and lime
3,102' - 3,821'	Chalky lime & shale
3,821' - 4,198'	Lime & shale
4,198' - 4,318'	Shale
4,318' - 4,966'	Shale & lime
4,966' - 5,006'	Lime
5,006' - 5,407'	Lime & shale
5,407' - 5,456'	Lime
5,456' - 5,625'	Lime & shale
5,625' - 5,664'	Sand
5,664' - 5,772'	Lime & shale

RECEIVED  
STATE CONSERVATION COMMISSION

APR 27 1960

CONSERVATION DIVISION  
Wichita, Kansas