

LEASE NAME Bobles

WELL NUMBER 4

4620 Ft. from S Section

3300 Ft. from E Section Line

SEC. 11 TWP. 31S RGE. 7W (E) or (W)

COUNTY Harper

Date Well Completed 8-25-80

Plugging Commenced 6-18-93

Plugging Completed 6-21-93

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR VALaEnergy, Inc.

ADDRESS Box 322 Haysville, Ks. 67060

PHONE# (316) 522-1560 OPERATORS LICENSE NO. 5822

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6-17-93 (date)

by M.L. Korphage and Steve Van Gieson (KCC District Agent's Name).

Is ACC-1 filed? yes If not, is well log attached? yes

Producing Formation Miss Depth to Top 4320 Bottom 4400 T.O. 4359

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	water	0	260	85/8	260	none
	water	0	4359		4358	2917

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each section.

Sand back to 4275, set CIBP at 3443, spot 2 sx cement plug, shoot pipe at 2917 and pull to 1250 ft, pump 35 sx plug, pull to 800 ft, pump 35 sx plug, pull to 310 ft and circulate to surface. Allied # 5825

Casing-has a tight spot at 3500 ft.

Name of Plugging Contractor VAL Energy Inc. License No. 5822

Address Box 322 Haysville, Ks. 67060

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: VAL Energy, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

K. Todd Allam (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) K Todd Allam

(Address) Wichita, Ks. 67212

SUBSCRIBED AND SWORN TO before me this 22 day of June, 19 93

Gary D. Stearns
Notary Public

My Commission Expires:
USE ONLY ONE SIDE OF EACH FORM



RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas
Form 6-1
Revised 05-88