


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Harper County, Sec. 11 Twp. 31S Rge. 7 ~~XX~~ (W)

Location as "NE/CNW/SW" or footage from lines C SW SW
Lease Owner Jayhawk Oil Company
Lease Name Rymph Well No. 1
Office Address 412 One Twenty Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 27, 1966
Application for plugging filed July 27, 1966
Application for plugging approved July 27, 1966
Plugging commenced July 27, 1966
Plugging completed July 27, 1966
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4,754 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	330'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 4,754 feet (R.T.D.) to 320 feet.
Set bottom plug at 320 feet and cemented with 30 sacks cement and 75 sacks
Davis gel. Filled hole with heavy rotary mud to 40 feet. Set top plug at
40 feet and cemented with 10 sacks cement = 2 sacks cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION
AUG 3 1966
8-3-66
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor H-30, Inc.
Address 200 North Main, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK
Maxine Coleman (employee of ~~owner~~ contractor) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Maxine Coleman
200 North Main, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of August, 19 66

My commission expires December 3, 1968.

Geraldine Hays
Geraldine Hays Notary Public.

KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **Jayhawk Oil Company**

SEC. **11** T. **31S.** R. **7W**
 LOC. **C SW SW**


FARM **Rymph** NO. **1**

TOTAL DEPTH **4,754'**
 COMM. **7/13/66** COMP. **7/27/66**

COUNTY **Harper**
 KANSAS

SHOT OR TREATED
 CONTRACTOR **H-30, Inc.**
 ISSUED

15-D77-30094-00-00



CASING
 20 10
 15 8 **5/8" cem w/200 sz**
 12 6
 13 5

ELEVATION **1567 KB**

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand	40
Sand & Clay	80
Shale & Red Bed	373
Red Bed, Shale & Shells	870
Shells, Shale Anhy. & Lime	1335
Shale, Lime & Shells	1545
Shells, Shale & Lime	1739
Lime & Shale	1945
Shale & Lime	2105
Lime & Shale	2700
Shale & Lime	3240
Lime & Shale	3359
Shale & Lime	3658
Sand & Shale	3690
Shale	3800
Shale & Lime	3905
Lime	4300
Lime & Shale	4366
Chert	4293
Miss. Shale & Lime	4557
Chert & Lime	4673
Lime & Shale	4723
Shale & Lime	4754
Rotary T. D.	4754

Electric Log Tops

Heebner	3274	-1707
Stalnaker	3558	-1991
Kansas City	3818	-2251
Mississippi	4350	-2783
Kinderhook Shale	4622	-3055
Simpson Sand	4750	-3183
Log T. D.	4753-	-3186

RECEIVED
 STATE CORPORATION COMMISSION

SEP 6 1966

CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify the above and foregoing to be a true and correct log of the above described well, as shown by the drilling reports.

H-30, INC.

Merle Britton

STATE OF KANSAS)
) SS:
 SEDGWICK COUNTY)

Subscribed and sworn to before me, a Notary Public in and for said county and state, this 2nd day of August, 1966.

Geraldine Hays
 Geraldine Hays, Notary Public

My Commission Expires:

12-3-68