

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Seward County, Sec. 23 Twp. 32S Rge. 28 (X) (W)

Location as "NE/CNW/SW" or footage from lines C NW SW

Lease Owner Thomas & Brewer

Lease Name SINGLEY Well No. 1

Office Address Box 985 - Liberal, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed March 13, 19 57

Application for plugging filed March 14, 19 57

Application for plugging approved March 14, 19 57

Plugging commenced March 14, 19 57

Plugging completed 11:30 PM March 14, 19 57

Reason for abandonment of well or producing formation

No commercial shows of oil or gas found.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes.

Name of Conservation Agent who supervised plugging of this well Mr. M. Rives

Producing formation None Depth to top Bottom Total Depth of Well 5760 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Red Beds	Red Shale	390	1500	13-3/8	442	None
Permian	Anhydrite	1500	2500	8-5/8	2472	898

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

A Halliburton plug was placed at 400', 35 sacks of Portland cement were run on top of this. The hole was then filled with mud to 20'. A Halliburton plug was set at 20', a sack of hulls was run on top of this plug, 15 sacks of Portland cement were run on top of this to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Midwestern Drilling Company
Address 303 South Virginia, Liberal, Kansas

STATE OF KANSAS, COUNTY OF SEWARD, ss.
Lloyd Henderson (employee of owner) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Lloyd Henderson
Box 985, Liberal, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 19th day of March, 19 57

My commission expires March 30, 1957

Mary Lane Notary Public.
RECEIVED
STATE CORPORATION COMMISSION

PLUGGING
FILE SEC 23 T 32 R 28W
BOOK PAGE 148 LINE 43

MAR 21 1957
3-21-57
CONSERVATION DIVISION

DRILLER'S LOG

Operator: Alamo Corporation
Lubbock Nat'l Bank Bldg.
Lubbock, Texas

Elevation:
Well Commenced: February 18, 1957

Contractor: Midwestern Drillers, Inc.
1206 Mid-Continent Bldg.
Tulsa, Oklahoma

Well Completed: March 14, 1957
Total Depth: 5,755' RB (D&A)

Lease Name: Singley No. 1

C.N.W. SW

Location: SW/4 Sec. 23, 32S, 28W
Meads County, Kansas

Qry

Casing Record: Surface - Set 442' of 13-3/8" casing with 500 sacks pozzix cement.
Intermediate - Set 2,472' of 8-5/8" casing with 200 sacks pozzix cement with 2% c.c.

FORMATION

DEPTH FROM ROTARY BUSHING

Sand, clay & red bed	0
Red bed and gypsum	462 Ran 4 1/2" of 13-3/8" casing
Gypsum & anhydrite and red bed	1270
Shale and anhydrite	1628
Shale and anhydrite	1895
Shale, anhydrite and lime	2095
Anhydrite, lime and shale	2160
Anhydrite and lime	2257
Lime and shale	2405
Lime, anhydrite and dolomite	2468
Lime and shale	2478 Ran 2,472' of 8-5/8" casing
Lime and shale	2658
Lime	2950
Chalk	3175
Lime and chalk	3335
Chalky lime	3385
Chalk, lime and shale	3755
Lime and shale	3880
Lime and shale	4184
Shale and lime	4334
Lime and shale	4484
Lime	4732
Lime and chert	4758
Lime	4775
Lime	4880
Lime and shale	4938
Lime	5035
Lime	5200
Lime	5382
Lime and shale	5431 Ran DST #1
Lime and shale	5443
Coring - Core #1	5482
Lime and shale	5557 Ran DST #2
Lime and shale	5671
Lime and chert	5698
Lime	5755 Ran Electric Log
	TD D&A

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above is a true and correct copy of Drillers Log of the Singley No. 1 well, of Alamo Corporation.

MIDWESTERN DRILLERS, INC.

PLUGGING
 FILE - SEC. 23 T. 32 R. 28W
 BOOK PAGE 148 LINE 43

By: F. W. Wyant
F. W. Wyant

Subscribed and sworn to before me this 20th day of March, 1957.

NOTARY PUBLIC
COMMISSION

MAR 25 1957

My commission expires:
February 21, 1961

CONSERVATION DIVISION
Wichita, Kansas

C. Williams
C. Williams (Notary Public)