

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

RECEIVED FORM CP-1
STATE CORPORATION COMMISSION 2/89

JUN 25 1991
6-25-91
CON DIVISION
Wichita, Kansas

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-119-20,220-00-00 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Lee Banks OPERATOR'S LICENSE NO. 05152

ADDRESS 200 West Douglas, Suite 550, Wichita, Ks 67202 PHONE # (316) 267-0783

LEASE (FARM) Hobart WELL NO. 1 WELL LOCATION C W/2 NW NE COUNTY Meade
LTD 5616
SEC. 12 TWP. 32S RGE. 28 (X) or (W) TOTAL DEPTH RTD 5622 PLUG BACK TD 5482

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. _____

SURFACE CASING SIZE 8-5/8 SET AT 1411 CEMENTED WITH 550 sx 1 1/2" cc, 150 sx 3/4" cc SACKS
50 sx Class H
CASING SIZE 4-1/2 SET AT 5539 CEMENTED WITH 150 50/50 Poz. SACKS

PERFORATED AT 5416 - 5420

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Bottom Plug 2 sacks Cottonseed Hulls & 20 sacks cement,

shoot casing loose, come up to 1440', cement 50 sacks, come up to 700', cement 40 sacks, come
up to 40', 10 sacks cement, cut off 8-5/8" and cap.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? no
(If not explain.) well drilled prior to ACO1

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Approximately July 8th

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Lee Banks or Ed Eves PHONE # (316) 267-0783

ADDRESS 200 W. Douglas, Suite 550, Wichita, KS 67202

PLUGGING CONTRACTOR Midwest Casing pulling Service LICENSE NO. 6497

ADDRESS Box F, Sublette, Kansas 67877 PHONE # (316) 675-8349

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: [Signature]
(Operator or Agent)

DATE: June 24, 1991

①

Joan Finney
Governor

Jim Robinson
Chairman

Keith R. Henley
Commissioner

Rachel C. Lipman
Commissioner

Judith McConnell
Executive Director

Brian J. Moline
General Counsel



Kansas Corporation Commission

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

June 25, 1991

Lee Banks
200 W. Douglas, Suite 550
Wichita, KS 67202

Hobart 1
API 15-119-20,220
C W2 NW NE
Sec. 12-32-28W
Meade County

Dear Operator:


This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). Failure to do so is punishable by an administrative penalty of up to \$1000.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,


David P. Williams
Production Supervisor

District: #1 304 W. McArtor
Dodge City, KS 67801
(316) 225-6760

Conservation Division
William R. Bryson
Director
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, Kansas 67202-1286
Telephone (316) 263-3238