

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-119-20,220-00-00

LEASE NAME Hobart

WELL NUMBER #1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

4620 Ft. from S Section Line

1820 Ft. from E Section Line

LEASE OPERATOR Lee Banks

SEC. 12 TWP. 32 RGE. 28 ~~XXX~~ or (W)

ADDRESS 200 W. Douglas, Ste. 550, Wichita, Ks. 67202 COUNTY Meade

PHONE#(316) 267-0783 OPERATORS LICENSE NO. 05152

Date Well Completed 3-13-1976

Character of Well gas

Plugging Commenced 7-3-1991

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 7-9-1991

The plugging proposal was approved on 6-26-1991 (date)

by Mr. Richard Lacy (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Morrow Depth to Top 5416' Bottom 5420' T.D. 5622'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED
STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put in	Pulled out
Surface				8 5/8"	1411'	0'
Production				4 1/2"	5539'	2840'

JUL 17 1991
7-17-91
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Pump 2 sks. hulls and 20 sks. cement to 5200' - pressured to 750 lbs.

Pump 50 sks. cement 1440' to 1300' - Mud 1300' to 700'

Pump 40 sks. cement 700' to 580' - Mud 580' to 40'

Put bridge and 10 sks. cement 40' to 3', Cut off 85/8 @ 3' and cap.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Midwest Casing Pulling Service License No. 6497

Address Box F, Sublette, Ks. 67877

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Lee Banks

STATE OF KANSAS COUNTY OF Haskell, ss.

I, Edgar J. Eves (Employee of Operator) or (~~XXXXXX~~) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.



(Signature) Edgar J. Eves

(Address) Box F, Sublette, Ks. 67877

SUBSCRIBED AND SWORN TO before me this 12th day of July, 1991

Sondral Eves
Notary Public

My Commission Expires: 12-6-92

15-119-20220-00-00

RECEIVED
STATE CORPORATION COMMISSION

C W/2 NW NE
SECTION 12-32S-28W
MEADE COUNTY, KANSAS

JUN 25 1991

CONSERVATION DIVISION
Wichita, Kansas

HOBART #1

CONTRACTOR: RINE DRILLING COMPANY

STARTED: FEBRUARY 29, 1976

COMPLETED: MARCH 13, 1976

L O G

Surface	0'	-	20'
Sand, Red Bed & Shale	20'	-	160'
Red Bed & Sand	160'	-	1401'
Anhydrite	1401'	-	1416'
Shale, Lime & Anhydrite	1416'	-	2563'
Lime & Shale	2563'	-	5622'

Totco - 1/2° @ 522'; 3/4° @ 1100'
 Ran 38 jts. 8 5/8" csg. @ 1411', cmt.
 w/550 sx. lite, 2% cc, 150 sx.
 common, 3% cc
 Totco - 1/2° @ 1416'
 Totco - 3/4° @ 1926'; 1/2° @ 2425'
 Totco - 1/2° @ 3022'; 1/4° @ 3527';
 1/4° @ 4505'


Ran 172 jts. new 10⁵⁰ K55, 5530', set
 @ 5541', K.B., Cement w/50 sx. clash
 150 sx. 50/50 poz. Plug down @ 7:10
 a.m., 3/13/76

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS

I, E. J. Rine, do hereby certify that the above is a true and accurate log of the Hobart #1, located C of W/2 of NW of NE of Section 12-32S-28W, Meade County, Kansas.


 E. J. Rine, President

Subscribed and sworn to before me this 15th day of March, 1976.


 Carol J. Hladik, Notary Public

My commission expires: 10/31/79

