

LEASE NAME Cummings-Elliott

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER #2

1980 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 12 TWP. 32S RGE. 28W (E) or (W)

COUNTY Meade

LEASE OPERATOR Lee Banks d/b/a Banks Oil Company

ADDRESS 200 W. Douglas, Suite 550

PHONE# (316) 267-0783 OPERATORS LICENSE NO. 05152

Date Well Completed 10-5-76

Character of Well O&G

Plugging Commenced 12-5-94

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12-13-94

The plugging proposal was approved on 12-94 (date)

by David P. Williams (R. Lacey on location during plugging) (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Toronto/Morrow Depth to Top 4314' Bottom 4320' T.D. PBTD 5344'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Toronto/Morrow	O&G	4314'	4320'	8 5/8 4 1/2"	1357' 5496'	none 2305'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Allied Cementing pumped bottom plug as follows. Pump 200 lbs hulls and 20 sks common cement and displace to 4250'. The casing was cut and pulled free at 2305'. Pulled casing to 1377' and Allied Cementing pumped 50 sks cement, pulled casing to 450' and pumped 40 sks. Pulled remainder of casing from well and topped off with 20 sks. All cement being 60/40 %.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Peters Drilling Co. License No. 03400

Address P.O. Box 742 Great Bend, Ks.

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Banks Oil

STATE OF KS. COUNTY OF Sedgwick, ss.

Michael G. Peters (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Michael G. Peters

(Address) 1912 VanBuren Great Bend, Ks.

SUBSCRIBED AND SWORN TO before me this 17 day of Dec, 19 94



My Commission Expires: 4:21-96

Norma Sander
 Notary Public

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 22 1994
 CONSERVATION DIVISION