

ATE OF KANSAS  
ATE CORPORATION COMMISSION  
D. S. Market, Room 2078  
chita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-119-20,579-0000

LEASE NAME Lowen D

WELL NUMBER #1

           Ft. from S Section Line

           Ft. from E Section Line

SEC. 36 TWP. 32S RGE. 28W (E) or (W)

COUNTY Meade

Date Well Completed           

Plugging Commenced 2-12-98

Plugging Completed 2-18-98

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

EASE OPERATOR Hugoton Energy Corporation

DRESS 4532 W. Jones Ave. Garden City, Ks. 67846

PHONE (316) 287-3811 OPERATORS LICENSE NO. 3871

Character of Well Gas

(Oil, Gas, D&A, S&D, Input, Water Supply Well)

The plugging proposal was approved on            (date)

by Gary Winters (KCC District Agent's Name).

Is ACO-1 filed?            If not, is well log attached?           

Producing Formation            Depth to Top            Bottom            T.D. 5800'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	1507'	None
				4-1/2"	5721'	3600'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from            feet to            feet each section. Plugged off bottom with sand to 5500' and 4 sacks cement. Shot pipe @4000', 3800', 3600', pulled up to 1530' and pumped 50 sks. cement and 10 sks. gel, pulled up to 600', pumped 40 sks. cement and 3 sks. gel, pumped 2 sks. gel and 35 sks. cement @40' and circulated to surface. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Hugoton Energy

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 6th day of March, 19 98

[Signature]  
Notary Public

My Commission Expires:           

RECEIVED  
KANSAS CORP. COM.  
29-98  
1998 MAR -9

