

15-077-10202-00-00

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Bison Energy Corporation

ADDRESS 9320 E. Central Wichita, Ks. 67206

PHONE# (316) 636-1801 OPERATORS LICENSE NO. 6581

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on June 15, 1993 (date)

by David P. Williams (KCC District Agent's Name).

Is ACO-1 filed? yes if not, is well log attached? _____

Producing Formation Mississippi Depth to Top 4298 Bottom 4573 T.D. 4719

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	SEE ATTACHED					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

SEE ATTACHED

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shawnee Well Service License No. 30346

Address 127 E. B St. Attica Ks.

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Bison Energy Corporation

STATE OF Kansas COUNTY OF Sedgwick, ss.

Steven C. Anderson, Bison Energy Corporation (Employee of Operator) or (Operator) of

above-described well, being first inducer, sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, the same as they are shown on the log.



RECEIVED
 STATE CORPORATION COMMISSION
 AUG 24 1993
 CONSERVATION DIVISION
 WICHITA, KANSAS

(Signature) [Signature]

(Address) 9320 E. Central Wichita, Ks. 67206

SUBSCRIBED AND SWORN TO before me this 23rd day of August, 19 93

8-24-93 Sondra J. Boyd
Notary Public
Sondra J. Boyd

My Commission Expires: May 13, 1995

WELL LOG

15-077-10202-00-00

COMPANY Phillips Petroleum Co.

SEC. 13 T. 31S R. 7W

FARM Palmer

NO. A-2

LOC. C NE SE


TOTAL DEPTH 4719'

COUNTY Harper

COMM. 1-27-64

COMP. 2-10-64

CONTRACTOR Garvey Drilling Company



CASING 8 5/8" @ 242' w/75 sx

4 1/2" @ 4453' w/110 sx

ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

140' Red Rock
 490' Red Bed and Shale
 1100' Shale
 1391' Shale and Lime
 1825' Lime
 1980' Shale and Lime
 2455' Shale and Lime Streaks
 2800' Lime and Shale
 2840' Lime
 3681' Lime and Shale
 3957' Lime
 4092' Lime and Shale
 4149' Lime
 4298' Lime and Shale
 4314' Mississippi
 4367' Mississippi Lime
 4569' Lime
 4700' Shale and Lime
 4719' Simpson Sand
 4719' RTD

RECEIVED
STATE CORPORATION COMMISSION

AUG 24 1993

CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION

AUG 24 1993

CONSERVATION DIVISION
Wichita, Kansas

7-27-93 Rigged up ELI Wireline, shot casing off at 2405', worked pipe for 25 min. shot pipe off at 2050' pulled 10 jts casing to fishing tool, laid down fishing tool and pulled 29 jts of casing total to 1135' from surface, pumped 30 sx cement, 14 BBLs water. Pulled 11 more jts, 40 jts total to 811' from surface, pumped 30 sx cement, 9 BBLs water, pulled 17 jts of casing to 267' from surface, pumped 68 sx cement, pulled 7 more jts for total of 64 jts. Topped off surface with 2 sx cement. Rigged down, moving to Newberry 3 1 to fish rod part.

15-077-10202-00-00