


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

HARPER County. Sec. 29 Twp. 31S Rge. 7W (#) (W)
Location as "NE/CNWSW" or footage from lines C N/2 NW SE
Lease Owner PETROLEUM, INC.
Lease Name MATHES "B" Well No. 1
Office Address R. R. 2, GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed MARCH 16 19 60
Application for plugging filed MARCH 16 19 60
Application for plugging approved MARCH 16 19 60
Plugging commenced MARCH 16 19 60
Plugging completed MARCH 16 19 60
Reason for abandonment of well or producing formation NO PRODUCIBLE ZONES

If a producing well is abandoned, date of last production NONE 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? FRED HAMPEL, PRETTY PRAIRIE, KANSAS

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 4706 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	248'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

MUD UP WITH HEAVY MUD TO 240', PUSHED DOWN 1/4 SACK HULLS TO 240' FOLLOWED BY WOODEN PLUG. PLACED 15 SACKS CEMENT THROUGH DRILL PIPE ON TO PLUG. MUD UP WITH HEAVY MUD TO 40' AND PLACED 1/4 SACK HULLS AT 40' FOLLOWED BY WOODEN PLUG AND 10 SACKS CEMENT TO BASE OF WELL CELLAR.

RECEIVED
STATE CORPORATION COMMISSION
MAR 29 1960
3-29-60
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor GARVEY DRILLING COMPANY
Address ROUTE 2, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
DON SEARLE (employee of owner) or (~~#####~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Searle
ROUTE 2, GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 25TH day of MARCH, 19 60

My commission expires APRIL 14, 1963 Arthur J. Miles Notary Public.



15-077-10181-00-00
WELL LOG

COMPANY PETROLEUM, INCORPORATED

SEC. 29 T. 31S R. 7W

FARM MATHES "B" NO. 1

LOC. C-N/2, NW, SE


TOTAL DEPTH 4706'

COUNTY HARPER CO., KANSAS

COMM. March 2, 1960

COMP. March 16, 1960

CONTRACTOR GARVEY DRILLING COMPANY



CASING 8 5/8" @ 248' w/200 sax.

ELEVATION 1485'

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

22	Clay & Sand
248	Surface soil, sand & shale
570	Red bed
1195	Shale & shells
1503	Shale & lime
2115	Lime & shale
3035	Shale & lime
3338	Lime & shale
3540	Shale
3760	Shale & lime streaks
3846	Lime & shale
4032	Lime
4320	Lime & shale
4500	Chert
4539	Lime
4556	Cherty lime
4631	Shale
4676	Lime & shale
4706	Simpson sand
4706	T. D.

RECEIVED
 STATE CORPORATION COMMISSION

MAR 29 1960

CONSERVATION DIVISION
 Wichita, Kansas

State of KANSAS }
 County of BARTON } ss:

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state that the above and foregoing is a true and correct copy of the log of the #1 MATHES "B" well.

Verne A. Morris

Subscribed and sworn to before me this 24th day of March 19 60

My Commission Expires: April 14, 1963

Arthur J. Mule
 NOTARY PUBLIC