

AFFIDAVIT AND COMPLETION FORM

ACO-1

This form must be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within five days after the completion of the well, regardless of how the well was completed. Circle one: Oil, gas, dry, SWD, OWWO, injection. Please type. Complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316) 263-3238.

OPERATOR Kimbark Oil & Gas Company API NO. 15-121-21.050-00-00  
 ADDRESS 1580 Lincoln St. #700 COUNTY Pratt  
Denver, CO 80203 FIELD BORTZ *w.c.*  
 \*\*CONTACT PERSON C. A. Hansen LEASE Bortz  
 PHONE (303) 839-5504  
 PURCHASER Central States Gas Company WELL NO. #1-25  
 ADDRESS 1700 Broadway #1600 WELL LOCATION C NE/4  
Denver, CO 80290 Ft. from \_\_\_\_\_ Line and  
 Ft. from \_\_\_\_\_ Line of

DRILLING CONTRACTOR DaMac Drilling Inc. RECEIVED the \_\_\_\_\_ SEC. 25 TWP. 28S RGE. 11W  
 ADDRESS Box 1164 STATE CORPORATION COMMISSION  
Great Bend, KS 67530 JUN 11 1982

PLUGGING CONTRACTOR \_\_\_\_\_ CONSERVATION DIVISION  
 ADDRESS \_\_\_\_\_ Wichita Kansas  
 TOTAL DEPTH 2950' PBTD \_\_\_\_\_  
 SPUD DATE 12/12/81 DATE COMPLETED 12/17/81  
 ELEV: GR 1800 DF 1810 KB 1811


WELL PLAT  
 (Quarter) or (Full) Section - Please indicate.

KCC   
 KGS

DRILLED WITH (~~XXXX~~) (ROTARY) (~~XXXX~~) TOOLS Report of all strings set — surface, intermediate, production, etc. (New)/(~~Used~~) casing.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8-5/8"	24	472	Regular	150	3% CaCl
					Lite	150	3% CaCl
Production	7-7/8"	4 1/2"	10.5	2939	50/50 poz	175	10% salt, 2% gel

LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
TUBING RECORD			2		2776-2780'
Size	Setting depth	Packer set at			
2-3/8"	2760'				

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD	
Amount and kind of material used	Depth interval treated
500 gal 15% acid	2776-2780'

TEST DATE:		PRODUCTION	
Date of first production <u>WOPL</u>	Producing method (flowing, pumping, gas lift, etc.) <u>flowing</u>	A.P.I. Gravity	
RATE OF PRODUCTION PER 24 HOURS	Oil _____ bbls.	Gas <u>250</u> MCF	Water <u>0</u> bbls.
Disposition of gas (vented, used on lease or sold) <u>to be sold</u>		Producing interval(s) <u>2776-2780'</u>	

\*\* The person who can be reached by phone regarding any questions concerning this information.  
 A witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

Name of lowest fresh water producing stratum \_\_\_\_\_ Depth \_\_\_\_\_  
 Estimated height of cement behind pipe \_\_\_\_\_

**WELL LOG**

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST#1 2571-2625' IO 15 min, ISI 30 min, FO 30 min, FSI 45 min. IHP 1271psi, IFP 172psi, ISIP 878psi, FFP 258psi, FSIP 899psi. FHP 1249psi, BHT 119°F Rec 620' muddy salt wtr.			Base of Florence	2070'
			Indian Cave	2576'
			Waubensee	2624'
			Tarkio	2765'

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

**A F F I D A V I T**

STATE OF Colorado, COUNTY OF Denver SS,

C. A. Hansen OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH, DEPOSES AND SAYS:

THAT HE IS Drlg & Production Mgr. FOR Kimbark Oil & Gas Company OPERATOR OF THE Bortz LEASE, AND IS DULY AUTHORIZED TO MAKE THIS AFFIDAVIT FOR AND ON BEHALF OF SAID OPERATOR, THAT WELL NO. 1-25 ON SAID LEASE HAS BEEN COMPLETED AS OF THE 11th DAY OF February 19 82, AND THAT ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.

(S) Nancy L. Engelman

SUBSCRIBED AND SWORN TO BEFORE ME THIS 9th DAY OF June 19 82

Nancy L. Engelman  
 NOTARY PUBLIC

MY COMMISSION EXPIRES: 2/2/86 1580 Lincoln St. #700 Denver, CO 80203