


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Pratt County, Sec. 8 Twp. 28S Rge. (E) 11 (W)
Location as "NE/CNW&SW" or footage from lines C/NW SW
Lease Owner Time Petroleum Company
Lease Name Goven "A" Well No. 1
Office Address 815 Union National, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 7 1965
Application for plugging filed August 7 1965
Application for plugging approved August 7 1965
Plugging commenced August 7 1965
Plugging completed August 8 1965
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie Elving, Pratt, Kansas
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8-5/8"	0	260'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged hole as follows: Plugged at 250' with 1/4 sack of hulls and 25 sacks of common cement and mud to 40'; plugged with 1/4 sacks of hulls and 10 sacks of cement. Also ran 2 sacks of cement in the rat hole and 2 sacks of cement in the mouse hole. Job completed at 12:15 A. M. August 8, 1965.

RECEIVED
STATE CORPORATION COMMISSION

AUG 13 1965 08-13-65

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Strata Drilling, Inc.
Address P. O. Box 355, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.
Jim B. McWilliams (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim B. McWilliams, Secy-Treas.
P. O. Box 355, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of August, 1965

My commission expires December 14, 1965

Elaine H. Taylor, Notary Public.

D R I L L E R S L O G

#1 Goyen "A"

CASING RECORD:
252.12' of used
8-5/8" casing.

COMPANY: Time Petroleum Company

DESCRIPTION: C/NW SW
Section 8-28S-11W
Pratt County, Kansas

TOTAL DEPTH:
4380'

COMMENCED: July 29, 1965

ELEVATION: 1790' RB
1785' GL

COMPLETED: August 8, 1965

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>	
Sand	0	170	Ran 252.12' of used 8-5/8" surface casing; set and cemented at 260' with 275 sacks of regular cement, 2% gel and 3% calcium chloride. Plug down at 7:45 P. M. July 30, 1965. Cement circulated.	
Red Bed	170	528		
Anhydrite	528	532		
Shale & Shells	532	849		
Sand, Shells & Red Bed	849	1500		
Lime & Shale	1500	1990		
Lime	1990	2170		
Lime & Shale	2170	2380		
Shale w/Lime Streaks	2380	2895		
Shale & Lime	2895	3173		
Shale & Lime	3173	3703		
Lime	3703	3922		
Lime & Shale	3922	4070		Ran one drill stem test.
Lime & Chert	4070	4084		
Cherty Lime	4084	4120		
Shale & Lime	4120	4240		
Lime	4240	4250		
Cherty Lime	4250	4271		
Lime, Shale & Chert	4271	4307		
Chert	4307	4330		
Cherty Lime	4330	4341	D. & A.	
Shale	4341	4350		
Chert & Lime	4350	4380		
Total Depth 4380'			Plugged hole as follows: Plugged at 250' with 1/4 sack of hulls and 25 sacks of common cement and mud to 40'; plugged with 1/4 sack of hulls and 10 sacks of cement. Also ran 2 sacks of cement in the rat hole and 2 sacks of cement in the mouse hole. Job completed at 12:15 A. M. August 8, 1965.	

STATE OF KANSAS)
) ss.
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RECEIVED
STATE CORPORATION COMMISSION

AUG 13 1965

CONSERVATION DIVISION
Wichita, Kansas

STRATA DRILLING, INC.

Jim B. McWilliams
Jim B. McWilliams, Secy-Treas.

Subscribed and sworn to before me this 10th day of August, 1965.

Elaine H. Taylor
Elaine H. Taylor, Notary Public

My Commission Expires:

December 14, 1965