

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-151-01-001-00-01

LEASE NAME Time-Goyen

WELL NUMBER A-1

2095 Ft. from S Section Line

4730 Ft. from E Section Line

SEC. 8 TWP. 28 RGE. 11 (E) or (W) (W)

COUNTY Pratt

Date Well Completed 8-7-65

Plugging Commenced 9-4-85

Plugging Completed 9-5-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Northern Natural Gas

ADDRESS Box 178, Cunningham, KS

PHONE#(316) 298-5111 OPERATORS LICENSE NO. KCC #5278

Character of Well Plugged

(Oil, Gas, D&A, SWD, Input, Water Supply Well) (Replugged)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? N/A If not, is well log attached? _____

Producing Formation None Depth to Top _____ Bottom _____ T.D. 4380.00

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	260	8 5/8"		None
		4377	3027	4 1/2"	1350'	Cemented in hole

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Cemented from 4377' to 3877' w/140 sk 50-50 poz-mix w/10# Gilsonite per/sk w/2% Gel. Drill pipe stuck in hole @ 3027'. Backed drill pipe off. Hole full of 40+ visc. Mud to 1230'. Cemented from 1230' to 1130' w/55 sks 50-50 poz-mix w/2% Gel thru the drill pipe. Hole full of 40+ visc. mud to 310'. Cemented thru drill pipe w/100 sks 50-50 poz-mix w/2% Gel to bottom of

(If additional description is necessary, use BACK of this form.)

cellar. Plug rathole w/15 sks Portland.

Name of Plugging Contractor Sterling Drilling Company License No. 5142

Address Sterling, KS 67579

STATE OF Kansas COUNTY OF Rice, ss.


Ben Horsch

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ben Horsch

(Address) Box 178, Cunningham, KS 67035



SUBSCRIBED AND SWORN TO before me this 26TH day of Sept, 19 85

Dianna L. Jacobs

Notary Public
STATE CORPORATION COMMISSION

My Commission Expires: 12/5/87

OCT 4 1985
10-04-85
CONSERVATION DIVISION
Wichita, Kansas

Form CP-4
Revised 08-84