

**Give All Information Completely
No Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas**

WELL PLUGGING RECORD

NORTE

	0	

**Locate well correctly on above
Section Plat**

Pratt County. Sec. 3 Twp. 28S Rge. 10E 11 (W)
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines C-E/2, SE, NW Sec. 3-28S11W
Lease Owner Gulf Oil Corporation
Lease Name F. H. Sellon Well No. 1
Office Address Box 544, Chase, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed February 22, 1944
Application for plugging filed December 23, 1949
Application for plugging approved January 6, 1950
Plugging commenced January 9, 1950
Plugging completed January 17, 1950
Reason for abandonment of well or producing formation No longer profitable

If a producing well is abandoned, date of last production..... August 11, 1949
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well..... C. D. Stough.....
Producing formation..... Lansing-Kansas City..... Depth to top..... 3504..... Bottom..... 3555..... Total Depth of Well..... 3555..... Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet tofeet for each plug set.

Bridged hole with crushed rock and dumped 5 sacks cement at 3500'. Pulled 5-1/2" casing and mudded hole to 250' and dumped 15 sacks cement at that point. Mudded hole to 30' of top and capped with 15 sacks cement.

RECEIVED
Conservation Div.

JAN 21 1950

01-21-50 JAN 21 1950
STATE CORPORATION
COMMISSION
KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to S. G. Sanderson (Mgr. Production Dept.)
Address Box 661, Tulsa, Oklahoma

STATE OF Kansas, COUNTY OF Rice, ss.
H. H. Wright (employee of owner) or (owner or operator) of the above-described well,
 being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) 11/11/2018

Box 544, Chase, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 19th day of January, 1956

My commission expires April 14, 1952

Notary Public.

22-7377-S 4-49-10M

PLUGGING
FILE SEC 3 T 78 R 11
BOOK 132 PAGE 30



GULF T 860-A09-43

SAND RECORD	Lansing-Kansas City Limb - 3504'-3555'	TOTAL DEPTH	3555'
-------------	--	-------------	-------

INITIAL PRODUCTION

Oil: "P" 203 barrels
Water: 12 barrels

Corrected gravity 32.8

CASING RECORD

SIZE	WEIGHT	THD.	CLASS	MAKE	SET AT DEPTH	SACKS CEMENT	LBS. CAL. CHLO.	PULLED	LEFT IN
8-5/8"	320	10-V	*	Lapw.	395'	132			395'
5-1/2"	104	C-N	New	Gals. st.	3510'	150			3510'
* 15 Jts. Glass B 3 Jts. Glass C-1									

- * 15 Jtn. Class B
- 3 Jtn. Class C-1

S—	3	T—	285	R—	117
				0	
				8/2	
				SE	
		0		NE	
Pratt County,					
Kansas					

ELEVATION— 1742' 15"
at 8'3" from 5-1/2" casing

ACIDIZED: 2-17-44 with 2,000 gallons
2-22-44 with 6,000 gallons
0 - 12

0 -	12	Cellar
	125	Sand and gravel
	400	Red bed and shells
	550	Red bed and shale
	1300	Shale and shells
	1495	Shale and lime
	1660	Lime, broken, and shale
	1700	Lime
	1725	Lime, hard
	1895	Lime
	1925	Sandy lime
	1985	Lime and shale
	2220	Lime
	2365	Lime, broken
	2535	Shale
	2680	Shale and lime, broken
	2825	Shale and lime
	2945	Lime, broken
	3045	Lime
	3120	Lime and Shale
	3410	Lime
	3430	Lime, broken sandy and shale
	3504	Shale
	3535	Lime
	3550 1/2	Lime, hard
	3555	"lime (total depth)

RECEIVED
JAN 7 X 1950

PLUGGING

FILE SEC-3-T-28-R(12)
BOOK PAGE 138 LINE 30