


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Flat

Pratt County, Sec. 25 Twp. 28 Rge. 11 XXX (W)
Location as "NE/CNW/SW" or footage from lines SW/SW/SW
Lease Owner L. C. Smitherman & Aurora
Lease Name Dyche Well No. 1
Office Address Box 627 - Augusta, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed 3-1-57 19__
Application for plugging filed 3-1-57 19__
Application for plugging approved 3-4-57 19__
Plugging commenced 3-1-57 19__
Plugging completed 3-2-57 19__
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production _____ 19__
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation Arbuckle Depth to top 4689 Bottom 4745 Total Depth of Well 4745 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Topeka	SW	3266	3320	0	0	0
Lansing	SW	3730	3945	0	0	0
Mississippi	SW	4256	4310	0	0	0
Viola	SW	4486	4592	0	0	0
Simpson	SW	4592	4689	0	0	0
Arbuckle	SW	4689	4745	0	0	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole was filled with heavy mud to 300'. Bottom plug was set at 300' with 20 sacks of cement. Top plug was set at 35' with 10 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor L. C. Smitherman Drilling Company
Address Box 627 - Augusta, Kansas

STATE OF KANSAS, COUNTY OF Butler, ss.
George R. Dent (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) George R. Dent
Box 627 AUGUSTA, KANSAS
(Address)

SUBSCRIBED AND SWORN to before me this 15 day of March, 1957

My commission expires March 31, 1958

Notary Public.
RECEIVED
STATE CORPORATION COMMISSION

PLUGGING
FILE SEC. 25 T. 28 R. 11w
BOOK PAGE 145 LINE 1

MAR 12 1957
03-19-57
CONSERVATION DIVISION
Wichita, Kansas

DYCHE #1

Company - Aurora Gasoline Company
 Contractor - L. C. Smitherman Drilling Co.
 Commenced - 2-12-57
 Completed - 3-1-57
 T.D. - 4745

Location: SW/SW/SW of Sec. 25-28S
 11W, Pratt County, Kans.
 Elevation:
 Casing: 380' - 8 5/8, cemented
 with 400 sacks.

FIGURES INDICATE BOTTOMS OF FORMATIONS:

0 -	170	Shale & sand
170 -	190	River Gravel
190 -	335	Shale, Lime & Red Bed
335 -	704	Shale
704 -	1770	Shale & Shells
1770 -	1805	Lime, broken
1805 -	1955	Lime W/shale Streaks
1955 -	2060	Lime, Ft. Riley
2060 -	2080	Shale
2080 -	2190	Lime
2190 -	2892	Lime W/shale Breaks
2892 -	2910	Lime
2910 -	3030	Lime W/shale Streaks
3030 -	3360	Lime W/shale Streaks (Sandy)
3360 -	3365	Shale
3365 -	3395	Shale & Lime Streaks
3395 -	3532	Lime (Sandy) W/shale Streaks
3532 -	3723	Lime & Shale
3723 -	3770	Lime (Lansing)
3770 -	3870	Lime (Kansas City)
3870 -	3910	Lime & Shale
3910 -	4226	Lime (Kansas City)
4226 -	4257	Mississippi Cong. (Shale)
4257 -	4397	Lime (Mississippi)
4397 -	4554	Shale W/Lime
4554 -	4616	Lime (Viola)
4616 -	4683	Simpson Sand
4683 -	4745	Lime (Arbuckle)

We hereby certify the above and foregoing to be a true and correct copy of the log on the Dyche #1, located in the SW/SW/SW of Section 25-28S-11W, Pratt County, Kansas.

L. C. Smitherman Drilling Company

George R. Dent

Subscribed and sworn to before me this 15th day of March, 1957.

Carl J. Zehn

 Notary Public

My Commission expires on March 31, 1958.

PLUGGING
 FILE SEC 25 T 28 R 11W
 BOOK PAGE 145 LI E. 1

RECEIVED
 CONSERVATION COMMISSION
 MAR 19 1957
 CONSERVATION DIVISION
 Wichita, Kansas