

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Pratt County, Sec. 22 Twp. 28S Rge. (E) 11(W)

Location as "NE/CNW/SW" or footage from lines C SW NW

Lease Owner Imperial Oil Company

Lease Name Marteney Well No. 1

Office Address 780 Fourth National Bldg., Wichita, Ks. 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed May 3 19 68

Application for plugging filed May 3 19 68

Application for plugging approved May 3 19 68

Plugging commenced May 3 19 68

Plugging completed May 3 19 68

Reason for abandonment of well or producing formation No commercial quantities of oil and/or gas were encountered.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving, Pratt, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4463 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface csg.	8 5/8"	at	390 feet		Not pulled

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 4463 feet to feet for each plug set.

Set first plug at 375 feet with 25 sacks cement.
Set second plug at 40 feet with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
MAY 10 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Imperial Oil Company
Address 780 Fourth National Bldg., Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
William A. Sladek (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. IMPERIAL OIL COMPANY

(Signature) William A. Sladek
William A. Sladek
780 Fourth National Bldg., Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of May, 19 68

My commission expires March 3, 1970
Mary J. Brown Notary Public.

DRILLER'S LOG

Imperial Oil Company
780 Fourth National Building
Wichita, Kansas 67202

Martenev No. 1
C SW NW Sec. 22-28S-11W
Pratt County, Kansas

Total Depth: 4463 ft.

Elevation: 1812 K.B.

Commenced: 4-18-68

Completed: 5-3-68
Dry Hole

Contractor: Imperial Oil Company, Rig #2

Casing Record: Set 8 5/8" surface casing at 390 feet with 300 sacks of cement.

Figures indicate bottom of formations:

	<u>Sample Tops:</u>
200' Sand	Towanda 1915 (- 103)
390' Red bed	Heebner 3488 (-1676)
1100' Shale-sand-Anhydrite	Brown Lime 3647 (-1835)
1630' Shale-shells	Lansing 3666 (-1854)
2355' Lime-shale	Mississippi 4122 (-2310)
2570' Shale-lime	Viola 4335 (-2523)
3768' Lime-shale	Simpson Sand 4440 (-2628)
4140' Lime	Rotary Total Depth 4463 (-2651)
4178' Lime-shale	
4280' Lime	
4328' Shale-lime	
4343' Core #1	
4351' Core #2	
4391' Lime-chert	
4442' Lime	
4447' Sand	
4463' Simpson	
<u>4463' Rotary Total Depth</u>	

RECEIVED
STATE CORPORATION COMMISSION
MAY 10 1968
CONSERVATION DIVISION
Wichita, Kansas

We hereby certify this to be a correct and accurate log of the above described well, as shown on the daily drilling reports.

IMPERIAL OIL COMPANY

By William A. Sladek
William A. Sladek

Subscribed and sworn to before me this 9th day of May, 1968.

Mary J. Brown
Mary J. Brown, Notary Public

My Commission Expires:
March 3, 1970