


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Locate well correctly on above
Section Plat

Pratt County, Sec. 22 Twp. 28S Rge. 11XX/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
70' SW of C NE NE

Lease Owner LOIL CORPORATION
Lease Name McGovney Well No. 1
Office Address Barrister Bldg., 1535 Grant St., Suite 270
Character of Well (Completed as Oil, Gas or Dry Hole) Denver
(8020) Colo.

Date Well completed 1-24-1980
Application for plugging filed 1-24-1980
Application for plugging approved 1-24-1980
Plugging commenced 1-24-1980
Plugging completed 1-24-1980

Reason for abandonment of well or producing formation
no commercial quantities of oil or gas encountered

If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well William T. Owen
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4560
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|--------------|---------|------|------|--------|--------|------------|
| surface hole | shale | surf | 246' | 8-5/8" | 244' | none |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Fluid to 540', plug, 40 sx
Fluid to 240', plug, 40 sx
Fluid to 40', plug, 10 sx
Rat hole 5 sx

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor D N B DRILLING, INC.
515 R. H. Garvey Building

Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.
Ella Priess (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Ella Priess
515 R. H. Garvey Bldg., Wichita, Ks. 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of January, 19 80

My commission expires April 30, 1983

Dorothy L. Schmidt
Dorothy L. Schmidt, Notary Public
STATE CORPORATION COMMISSION

DOROTHY L. SCHMIDT
STATE NOTARY PUBLIC
Sedgwick County, Kansas
My Appt. Exp. April 30, 1983

DRILLER'S LOG

LOIL CORPORATION
No. 1 McGovney
70' SW of C NE NE
Sec. 22-28S-11W
Pratt Co., Ks.

Commenced: 1-14-80
Completed: 1-24-80

Surface Casing: 244' of 8-5/8"
cemented w/225 sx common.

FORMATION

DEPTH

| | |
|--------------|-----------------|
| Surface Hole | 0 - 246 |
| Sand & Shale | 246 - 1020 |
| Shale & Salt | 1020 - 1495 |
| Lime | 1495 - 1635 |
| Shale | 1635 - 1853 |
| Shale & Lime | 1853 - 2080 |
| Lime & Shale | 2080 - 2310 |
| Shale & Lime | 2310 - 3176 |
| Lime & Shale | 3176 - 3500 |
| Shale & Lime | 3500 - 3636 |
| Lime | 3636 - 3788 |
| Lime & Shale | 3788 - 4114 |
| Mississippi | 4114 - 4121 |
| Kinderhook | 4121 - 4181 |
| Shale & Lime | 4181 - 4216 |
| Lime | 4216 - 4386 |
| Lime & Shale | 4386 - 4465 |
| Shale & Lime | 4465 - 4491 |
| Lime | 4491 - 4560 RTD |

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

Ella Priess

Ella Priess

RECEIVED

STATE CORPORATION COMMISSION

FEB 28 1980

STATE OF KANSAS: ss:

CONSERVATION DIVISION

Subscribed and sworn to before me this 25th day of January, 1980

DOROTHY L. SCHMIDT
STATE NOTARY PUBLIC
Sedgwick County, Kansas
My Appt. Exp. April 30, 1983

Dorothy L. Schmidt

Dorothy L. Schmidt, Notary Public