

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-151-21,858-0000

LEASE NAME County Farm

WELL NUMBER #1

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

4290 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 15 TWP. 28 RGE. 13 (E) or (W)

COUNTY Pratt

LEASE OPERATOR Michael W. Kirkman

ADDRESS Box 982, Pratt, Ks. 67124

PHONE# 316-672-7471 OPERATORS LICENSE NO. 30043

Date Well Completed \_\_\_\_\_

Character of Well Oil

Plugging Commenced 6-21-89

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 7-7-89

The plugging proposal was approved on \_\_\_\_\_ (date)

by Steve Durrant (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? With application

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4600'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	938'	None
				4-1/2"	4555'	3,117.41'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set. Dumped sand to 3840' and 5 sacks cement. Shot casing at 3400' & 3100'. Pulled 75 jts of 4-1/2" casing. B.J.Titan plugged well with 3 sacks hulls, 50 sacks cement 10 sack gel, released plug and pumped 100 sacks 60/40 pozmix cement with 6% gel. Maximum pressure was 200 psi and shutin 100 psi.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Michael W. Kirkman

STATE OF Kansas COUNTY OF Barton, ss.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 19 1989  
7-19-89  
CONSERVATION DIVISION  
Wichita, Kansas

James W. Rockhold (Employee of Operator) Warrant Operator of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 18th day of July, 1989

My Commission Expires \_\_\_\_\_

STATE NOTARY PUBLIC  
KANSAS  
IONA M. LEATHERMAN  
Barton County, Kansas  
My Appt. Exp. 7-26-91

Notary Public