


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Pratt County. Sec. 7 Twp. 28 Rge. (E) 11 (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C NE $\frac{1}{4}$
Lease Owner E. G. Holl
Lease Name Goyen Well No. 2
Office Address 6127 E. Kellogg, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 30, 19 61
Application for plugging filed Yes 19
Application for plugging approved Yes 19
Plugging commenced June 30 19 61
Plugging completed June 30, July 1 19 61
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Broadfoot
Producing formation Depth to top Bottom Total Depth of Well 2351 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				<u>7" casing</u>	<u>365'</u>	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Measured T.D. 2451'
Heavy mud to 240'
Plug with 20 sacks on top
Mud to 40'
Plug with 8 sacks on top
2 sacks of cement in rat hole

RECEIVED
STATE CORPORATION COMMISSION
JUL 14 1961
7-14-61
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to
Address

STATE OF Kansas, COUNTY OF Sedgwick, ss.
L. C. McLaughlin (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. C. McLaughlin
(Address)

SUBSCRIBED AND SWORN to before me this 13th day of July, 1961
J. E. Canaday, Jr.
Notary Public.

My commission expires Sept 18, 1962
28-8278-S 4-50-10M

INVOICED

DATE 7/18/61
INV. NO. 3386-W

RECEIVED
STATE CORPORATION COMMISSION

JUL 14 1961

CONSERVATION DIVISION
Wichita, Kansas

WELL LOG

Date Commenced June 18, 1961
Date Completed June 29, 1961

F. G. Holl
Goyen No. 2
C NE $\frac{1}{4}$ 7-28S-11W
Pratt County, Kansas

Elevation 1802 D.F.

0' - 125'	Surface soil
125' - 155'	Sand
155' - 308'	Redbed
308' - 748'	Shale & lime
748' - 903'	Anhydrite
903' - 1190'	Shale & lime
1190' - 1510'	Salt & shale
1510' - 1754'	Anhydrite & shale
1754' - 1920'	Dolomite & shale
1926' - 2050'	Lime & shale
2050' - 2260'	Shale & lime
2260' - 2351'	Lime with shale streaks

Base Wellington	1758 (444)
Winfield	1820 (-18)
Fort Riley	1932 (130)
Base Fort Riley	2030 (-227)
Cottonwood	2264 (-464)
Glenrock	2392 (-590)

Casing: Surface 7 inch set
@ 366 feet with 250 sacks
cement.

AFFIDAVIT

State of Kansas County of Sedgwick

I, True Knowles, Geologist, do swear that the statements and
matters herein contained are true to the best of my knowledge.

F. G. HOLL

By: True Knowles
Geologist

Subscribed and sworn to before me this 13 day of July, 1961.

B. E. Canaday
Notary Public


My Commission Expires: Sept 18, 1962

10

... ..
... ..
... ..
... ..
... ..
... ..
... ..
... ..
... ..
... ..

.....

.....



.....
.....
.....
.....