

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

15-077-10181-00-00

APR 6 1960
4-6-60
CONSERVATION DIVISION
Wichita, Kansas

File No. _____ County: Harper
Location: NW. NW. NE. Sec. 29 Twp. 31 Rge. 7 (E) (W) X
Name of Field: Wildcat Total Depth: 4706'

I have this date completed supervision of plugging of:

Lease Name: Mathis "B" Well No. 1

Operator's Full Name: Petroleum Inc.

Complete Address: 325 N. Broadway Wichita, Ks

Plugging Contractor: Harvey Drilling Co.

Address: Route 2 Great Bend License No. _____

Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A X

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No X

If yes how long? _____ Reason: _____

Operation Completed: Hour 6:30 P.M. Day 16 Month March Year 1960

The above well was plugged as follows:

J. D. 4706' - S. P. 8 5/8" - 248' cwc - 2002
Heavy mud to to 240' set plug used 1/2" shells
15 s. cement through drill pipe, mud to 40'
set plug used 1/2" shells 10 s. cement to
base of cellar.
Bridge rat hole use shells + 2 s. cement
below cultivation dept.

Signed: Fred W Hampel
Conservation Division Agent

Reviewed: J. Lewis Brock
Field Supervisor

Remarks:

INVOICED
DATE 4/7/60
INV. NO. 1164-w