

R

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 19 1973
11-19-73
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-077-10183-00-00

Operator's Full Name Continental Oil Co

Complete Address 3535 NW 58th St Oklahoma City, OK

Lease Name L.E. Mathes Well No. 6

Location NE/SE/NE Sec. 29 Twp. 31 Rge. 7 (E) (W)

County Harper Total Depth 4726

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Russ Casing Pulling Co Inc

Address Box 1082 Great Bend, KS License No. 623

Operation Completed: Hour 10:00 AM Day 16 Month 11 Year 1973

The above well was plugged as follows:

273 ft 8 5/8 surface cemented with 200 sacks. 4726 ft 5 1/2 long string
cemented with 250 sacks. Top perf. 4675 ft. Sand to 4600 ft, 5 sacks
cement with bailer. Pulled 3630 ft 5 1/2. Set 10 ft rock bridge at
320 ft. Fill hole with 5 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED
DATE 11/20/73
INV. NO. 8186-W