

4
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-077-10186-00-00

RECEIVED
STATE CORPORATION COMMISSION

APR 12 1963
4-12-63
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Continental Oil Co.

Complete Address: Box 30, Lyons, Kansas

Lease Name Mathes Well No. # 3

Location NE SW NE
1651 NL 1650 EL Sec. 29 Twp. 31 Rge. 7 (E) (W) W

County Harper Total Depth 4720

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 5:30PM Day 9th Month April Year 1963

The Above well was plugged as follows:

5 1/2" long string plugged back to 4691', cemented with 250 sacks.

Perferated from 4667' to 4672', 237' of 8 5/8" surface pipe cement
circulated. Sanded to 4650', cemented with 5 sacks. Hole was filled to
226' with mud, 10' rock bridge, cemented with 20 sacks. Hole filled
to 40', 10' rock bridge, cemented with 10 sacks to base cellar.

3229' of 5 1/2" recovered from hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4/12/63

INV. NO. 10887-14

Signed: Audie Elving
Well Plugging Supervisor