

15-077-00818-00-00

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION

JUL 23 1975  
7-23-75  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Mobil Oil Corp

Complete Address Box 1934 Oklahoma City, OK

Lease Name Fredrick W. Grabbs, B Well No. 4

Location NE/NW/SE Sec. 13 Twp. 31 Rge. 9 (E) (W)W

County Harper Total Depth 4490

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling Co

Address Box 176 Chase, KS License No. 683

Operation Completed: Hour 11:00 AM Day 21 Month 7 Year 1975

The above well was plugged as follows:

230 ft 9 5/8 surface cemented with 250 sacks. 4481 ft 5 1/2 long string  
cemented with 250 sacks. Top perf. 4400 ft. Sand to 4350 ft, 7 sacks  
cement with bailer. Pulled 2879 ft 5 1/2. Set 10 ft rock bridge at  
240 ft. Fill hole with 4 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED

DATE 7/23/75

INV. NO. 1669-W