

K KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-077-00870-00-00

RECEIVED
STATE CORPORATION COMMISSION

AUG 8 1963
8-8-63
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name H. W. Bass & Sons Inc.

Complete Address: 1150 Mercantile Dallas Bldg., Dallas, Texas

Lease Name Leo Ryan Well No. # 3

Location NE SW SW Sec. 13 Twp. 31 Rge. 9 (E) (W) W

County Harper Total Depth 4455

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling Co.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 7:30PM Day 5th Month August Year 1963

The Above well was plugged as follows:

191' of 8 5/8" surface pipe, cemented with 150 sacks. 4453' of 5 1/2" long
string, cement unknown. Plugged back to 4405'. Top perferation 4400',
Sanded to 4380', cemented with 5 sacks. Hole was bailed down and plug
was set at 225', with a 10' rock bridge, cemented with 20 sacks. Hole
was filled with mud to 40', 10' rock bridge, cemented with 10 sacks to
base cellar.

2717' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 8/8/63
INV. NO. 7537-W