

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 15 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name McAdams Pipe & Supply Co.

Complete Address Box 960, Bristow, Oklahoma

Lease Name Holmes Well No. 1

Location 100' W. of C NW SW Sec. 2 Twp. 33 Rge. 30 (E) (W)

County Meade Total Depth 5764' 5774'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Sargent Casing Pulling

Address Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 2:00PM Day 10 Month 5 Year 1974

The above well was plugged as follows:

13 3/8" to 687' circulated w/cement. 8 5/8" to 2681' cemented.

5 1/2" to 5760' cemented. Top perforations 5686'

Plug bottom w/ 20 sacks cement. Top of cement 5550'

Mud 5550' to 650' Spotted 50 sacks cement 650' to 550'

Mud 550' to 40' Plug, hulls & 20 sacks cement 40' to 0'

Company Pump

Pulled 2851' of 5 1/2" casing & 851' of 8 5/8" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 5/15/74

INV. NO. 9124-W