

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT
STATE CORPORATION COMMISSION

RECEIVED
APR 23 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name McAdams Pipe & Supply Company

Complete Address Box 960, Bristow, Oklahoma 74010

Lease Name Holmes Well No. 2

Location C SW NW Sec. 2 Twp. 33 Rge. 30 (E) (W)

County Meade Total Depth 6150'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Sargent Casing Pulling Co.

Address Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 2:00 PM Day 19 Month 4 Year 1974

The above well was plugged as follows:

9 5/8" to 1583' drilled w/ cement. 5 1/2" to 6134' cemented.

Top perforations 5671' Plug bottom w/ 20 sacks cement.

Top of cement 5550' Mud 5550' to 900'

Spotted 35 sacks cement 900' to 800' Mud 800' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'. Company Pump

Pulled 2851' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 4/23/74

INV. NO. 8967-W