

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
FEB 6 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Mc Adams Pipe And Supply Co.

Complete Address Box 960, Bristow, Oklahoma

Lease Name Holmes Well No. 6

Location C NE NW Sec. 2 Twp. 33 Rge. 30 (E) (W)

County Meade Total Depth 5838'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Sargents Casing Pulling Co.

Address Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 10:00AM Day 1 Month 2 Year 1974

The above well was plugged as follows:

8 5/8" to 1600' circulated w/ cement. 5 1/2" casing to 5825' cemented

Top perforations 5643' Plug bottom w/ 20 sacks cement

Top of cement 5450' Mud 5450' to 1000'

Spotted 35 sacks cement 1000' to 900' Mud 900' to 45'

Plug, Halls & 15 sacks cement 45' to 0'. Company Pump

Pulled 3639' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 2/8/74

INV. NO. 8542-W

Signed: Edgar G. King
Well Plugging Supervisor