

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 12 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Mc. Adams Pipe & Supply Company

Complete Address Box 960, Bristow, Oklahoma

Lease Name Holmes Well No. 4

Location C SW NE Sec. 2 Twp. 33 Rge. 30 (E) (W)

County Meade Total Depth 5850'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated

Plugging Contractor Sargents Casing Pulling

Address Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 1:30Pm Day 1 Month 3 Year 1974

The above well was plugged as follows:

- 9 5/8" to 1609' circulated w/ cement. 5 1/2" to 5828' cemented.
- Top perforations 5674' Plug bottom w/ 20 sacks cement.
- Top of cement 5550' Mud 5550' to 1000'
- Spotted 35 sacks cement 1000' to 900' Mud 900' to 45'
- Plug, Hulls & 15 sacks cement 45' to 0'. Company Pump
- Pulled 2792' of 5 1/2" casing.

~~INVOICED~~

I hereby certify that the above well was plugged as herein stated.

DATE 3/12/74

INV. NO. 8744-W

Signed: [Signature]  
Well Plugging Supervisor