

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
MAR 26 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name McAdams Pipe & Supply Company

Complete Address Box 960, Bristow, Oklahoma

Lease Name Holmes Well No. 11

Location G NE NE Sec. 2 Twp. 33 Rge. 30 (E) (W)

County Meade Total Depth 5820'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Sargent Casing Pulling

Address Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 2:30PM Day 22 Month 3 Year 1974

The above well was plugged as follows:

8 5/8" to 1600' circulated w/ cement. 5 1/2" to 5806' cemented.

Top perforations 5667' Plug bottom w/ 20 sacks cement.

Top of cement 5500' Mud 5500' to 800'

Spotted 35 sacks cement 800' to 700' Mud 700' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'. Company Pump

Pulled 2823' of 5 1/2" casing

NOTICED

I hereby certify that the above well was plugged as herein stated.

DATE 3/28/74
INV. NO. 8810-W

Signed: [Signature]
Well Plugging Supervisor