

15-119-10029-0000 R

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 18 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name McAdams Pipe & Supply Company
Complete Address Box 960, Bristow, Oklahoma 74010
Lease Name Leslie Well No. 4
Location C NE SE Sec. 3 Twp. 33 Rge. 30 (E) (W)
County Meade Total Depth 5890'
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Sargent Casing Pulling
Address Box 506,, Liberal, Kansas License No. 511
Operation Completed: Hour 4:30Pm Day 12 Month 4 Year 1974

The above well was plugged as follows:

8 5/8" to 1609' circulated w/ cement. 5 1/2" to 5825' cemented.
Top perforations 5700' Plug bottom w/ 20 sacks cement.
Top of cement 5550' Mud 5550' to 800'
Spotted 35 sacks cement 800' to 700' Mud 700' to 45'
Plug, Halls & 15 sacks cement 45' to 0'. Company Pump
Pulled 3350' of 5 1/2" casing.

INVOICED

I hereby certify that the above well was plugged as herein stated.

DATE 4/18/74

INV. NO. 8949-W

Signed: [Signature]
Well Plugging Supervisor