

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 3 - 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name McAdams Pipe & Supply Co.

Complete Address Box 960, Bristow, Oklahoma

Lease Name Leslie Well No. 1

Location C SW NE Sec. 3 Twp. 33 Rge. 30 (E) (W)

County Meade Total Depth 5760'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Sargents Casing Pulling

Address Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 5:00PM Day 30 Month 4 Year 1974

The above well was plugged as follows:

13 3/8" to 642' circulated w/ cement. 8 5/8" to 2674' cemented.

5 1/2" to 5745' cemented. Top perforations 5668'

Plug bottom w/ 20 sacks cement Top of cement 5550'

Mud 5550' to 650' Spotted 50 sacks cement 650' to 550'

Mud 550' to 40' Plug, Hulls & 20 sacks cement 40' to 0'

Company Pump

Pulled 2846' of 5 1/2" casing & 1050' of 8 5/8" Casing.

INVOICED

I hereby certify that the above well was plugged as herein stated.

DATE 5/8/74
INV. NO. 9042-W

Signed: [Signature]
Well Plugging Supervisor