

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 1 - 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name McAdams Pipe & Supply Co.

Complete Address Box 960, Bristow, Oklahoma 74010

Lease Name Kelly Well No. 1

Location C NE SW Sec. 3 Twp. 33 Rge. 30 (E) (W)

County Meade Total Depth 5842'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Sargent Casing Pulling

Address Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 10:00AM Day 26 Month 4 Year 1974

The above well was plugged as follows:

13 3/8" to 651' circulated w/ cement. 8 5/8" to 2675' cemented.

5 1/2" to 5811' cemented. Top perforations 5676'

Plug bottom w/ 20 sacks cement. Top of cement 5550'

Mud 5550' to 900' Spotted 50 sacks cement 900' to 800'

Mud 800' to 49' Bridge & 20 sacks cement 40' to 0'.

Company Pump _____

Pulled 2854' of 5 1/2" & 701' of 8 5/8" casing.

INVOICED

I hereby certify that the above well was plugged as herein stated.

DATE 5/1/74

INV. NO. 9028-W

Signed: [Signature]
Well Plugging Supervisor