

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

Authority Sept 15, 1980
API Number 15 - - (of this well)

Operator's Full Name Buttonwood Petroleum
Complete Address PO Box 1578, Liberal, Kansas
Lease Name Jennings Well No. 1
Location 150 F. 11/2 Sec. 3 Twp. 33 Rge. 30 (E) (W)
County Meade Total Depth 5910
Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Sargent's Casing Pulling
Address Liberal Kansas License No. 511

Operation Completed: Hour 12:00 noon Day 17 Month Sept Year 1980

The above well was plugged as follows:

There 1492' of 8/8" surface casing. C.C.
4 1/2" set 4635' plug back 4571'. Separations
were 4526-4524. 1st plug on bottom with
10 lbs cement + 1 lbs pills. 2nd plug at
1500' with 35 lbs cement. 3rd plug at 700'
with 25 lbs cement. 4th plug at 40-0 with
10 lbs cement. There was 2700' of 4 1/2"
Casing salvaged.

I hereby certify that the above well was plugged as herein stated.

Signed: Chance Howard
Well Plugging Supervisor

RECEIVED
STATE CORPORATION COMMISSION
SEP 18 1980
CONSERVATION DIVISION
Wichita, Kansas

INVOICED
DATE 9-18-80
INV. NO. 3166-w