

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 8 - 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name McAdams Pipe & Supply Co.

Complete Address Box 960, Bristow, Oklahoma

Lease Name Leslie "A" Well No. 1

Location C SE NW Sec. 3 Twp. 33 Rge. 30 (E) (W)

County Meade Total Depth 5820'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Sargent Gasing Pulling

Address Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 2:00PM Day 4 Month 5 Year 1974

The above well was plugged as follows:

13 3/8" to 672' circulated w/ cement. 8 5/8" to 2660' Cemented.

5 1/2" to 5800' cemented. Top perforations 5659'

Plug bottom w/ 20 sacks cement. Top of cement 5550'

Mud 5550' to 600' Spotted 50 sacks cement 600' to 500'

Mud 500' to 40' Plug, Hulls & 20 Sacks cement 40' to 0'.

Pulled 853' of 8 5/8" casing & 3834' of 5 1/2" casing.

Company Pump _____

INVOICED hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

DATE 5/8/74

INV. NO. 9070-W