

TU

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: Meade  
Location: NE NE NE Sec. 4 Twp. 33 Rge. 30 (E) (W)  
Name of Field: \_\_\_\_\_ Total Depth: 5730

I have this date completed supervision of plugging of:

Lease Name: E. L. Richardson Well No. 2  
Operator's Full Name: Sunray - Mill - Continent Oil Co.  
Complete Address: Wichita, Kans  
Plugging Contractor: Shurt & Reeves Casing Pulling Co.  
Address: Ottawa, City - Okla. License No. 49  
Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 11am Day 14 Month January Year 1961

The above well was plugged as follows:

2681' of 8 5/8" surface casing - 638' of 13 3/8" surface casing.  
5 1/2" set 5685. Top perf. 5620'. Hole was mudded to  
5550' and 5 sack cement dumped on sand. 5 1/2" pulled.  
Hole was mudded to 600'. 20 sack cement dumped  
on 10' ledge set from 600' to 590'. Hole mudded to 40'.  
Rock ledge set from 40' to 30'. 10 sack cement dumped  
on ledge to base of collar.

Signed: [Signature]  
Conservation Division Agent

Reviewed: J. Lewis Brock  
Field Supervisor

RECEIVED  
STATE CORPORATION COMMISSION

Remarks:

JAN 26 1961

CONSERVATION DIVISION  
Wichita, Kansas

DATE 1/20/61  
INV. NO. 2517-W