



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

NOV 17 1965  
 11-17-65  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Tracy \_\_\_\_\_ of Horizon Oil & Gas Co. \_\_\_\_\_ has this  
 date requested permission to plug the following described well:

Mr. Tracy \_\_\_\_\_ guarantees payment of the plugging fee.

Operator's full Name: Horizon Oil & Gas Co.

Complete Address: Box 7 Spearman, Texas

Lease Name: Hallock Well No. # 1-30

Location: C NW SE Sec. 30 Twp. 32S Rge. 28 (E) (W)

County Meade Total Depth 5780' Oil Well X


Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A X Lost Hole \_\_\_\_\_

Mr. Tracy \_\_\_\_\_ was instructed to plug the well as follows:

8 5/8"-1520' Circulated w/cement. 2 7/8"-5780' Cemented.

Plug bottom w/steel bridge plug, set plug at 5100' and 2 S<sub>ax</sub>. cement on  
top bridge plug. Mud 5100' to 700' Spotted 35 S<sub>ax</sub>. cement 700' to  
600'. Mud 600' to 45' Plug, 15 S<sub>ax</sub>. cement 45' to 0

Very truly yours,

  
 Conservation Division Agent