



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

RECEIVED  
 STATE CORPORATION COMMISSION

APR 25 1962  
 4-25-62  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

I have this date April 21, 1962, ~~XXXXX~~ authorized the following plugging operation:

Operator's full Name: Petroleum, Inc.

Complete Address: 352 N. Broadway, Wichita, Kansas

Lease Name: Gleaves Well No. 1

Location: SW SW SE Sec. 32 Twp. 32 Rge. 28 (E)(W)

County: Meade Total Depth: 5700

Oil Well      Gas Well      Input Well      SWD Well     

D & A X Other well as hereafter indicated:     

Operator was instructed to plug well as follows:

8 5/8" 1568' Gwc.

Fill hole with heavy mud to 1500'. Set plug & displace 50 sax cement thru drill pipe with pump truck. Mud to 35', 1/2 sax hulls, plug, & 10 sax cement, cementing to base of cellar.

Very truly yours,



*Lawrence*  
 Conservation Division Agent