

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS

JEWEL M. OGDEN, Director

GEORGE DOCKING Governor  
MARION BEATTY Chairman  
HARRY G. WILES Commissioner  
RICHARD C. BYRD Commissioner  
RAYMOND B. HARVEY Secretary  
CLYDE E. MILLIGAN Counsel

RECEIVED  
STATE CORPORATION COMMISSION

SEP 10 1959  
9-10-59  
CONSERVATION DIVISION  
Wichita, Kansas

Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

I have this date Sept 5, 1959, authorized the following plugging operation:

Operator's Full Name: Shelly Oil Company

Complete Address: Box 391 Hutchinson Kansas

Lease Name: Williams Well No. 1

Location: NE. SE. NW. Sec. 13 Twp. 31 Rge. 7 (E) (W) W

County: Harpur Total Depth: 4731

Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Operator was instructed to plug well as follows:

J.D. 4731'-S.P. 8 7/8'-560' CWC 300 ay.

5 1/2" 4702-150 ay - P.B. 3890'-Perf. 3877'

3884'. Sand to 3850' add 5' cement with tails

Lump mud from 640' to 250'

10-R.B. 250'-20 ay C. mud to 40'

10-R.B. 40'-10 ay C

Very truly yours,

Signed: Fred W. Hampel  
Conservation Division Agent