


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Meade County, Sec. 20 Twp. 33S Rge. 30W (E) (W)

Location as "NE/CNW&SW¼" or footage from lines C NE NW
Lease Owner W. J. Coppinger et al
Lease Name Mayer Well No. 1
Office Address 717 Union Natl Bldg., Wichita 2, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed R T D 12-4- 19 62
Application for plugging filed January 8 19 63
Application for plugging approved January 9 19 63
Plugging commenced January 28, 19 63
Plugging completed March 1 19 63
Reason for abandonment of well or producing formation dry



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott, Liberal, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 6225 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS.

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	1151	none
				4-1/2"	5800	4961

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Moved on and started cleaning cellar and blowing down well.
Sanded to 5650' and dumped 5 sax cement, worked pipe and loaded hole with water
Worked pipe and finished cleaning out cellar; broke off head; worked on equipment.
Pulled pipe and dropped pipe; started fishing
Fished pipe, worked pipe and holed bridge @ 400'. Spudded on bridge.
Worked and shot pipe @ 3967'. Pulled pipe
Pulled rest of pipe; plugged well with mud and rock bridge @ 750'.
Dumped 35 sax cement; filled hole and rock bridge.
Plugged well at 50' and capped with 15 sax cement.

RECEIVED
STATE CORPORATION COMMISSION

MAR 13 1963

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.
Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
W. J. Coppinger (employee of owner or owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. J. Coppinger
717 Union Natl Bldg., Wichita
(Address)

SUBSCRIBED AND SWORN to before me this 6th day of March, 19 63

My commission expires

May 15, 1966

Mayree Branstetter
(Mayree Branstetter) Notary Public.



MEYER #1
NE NW SEC
Meade County, Kansas

Rigged up Rotary Tools 11/8/62

Ran 48 Jts. (1461.84') of 8-5/8" 24# New Casing. Set @ 1458' and cemented with 425 sacks Pozmix w/2% cc and 400 sacks Common w/2% cc. Ran 37 Jts. of 9.5# J-55 and 45 Jts. of 10.5# J-55 (5818.99') new Casing. Set @ 5800' w/150 sacks Pozmix.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Sand	0	2501'
Sand & Red Beds	250	1030'
Red Bed & Shells	1030	1458'
Shale	1458	2604'
Shale & Lime	2604	2836'
Lime	2836	2936'
Lime & Shale	2936	3960'
Lime	3960	4080'
Lime & Shale	4080	4461'
Lime	4461	4541'
Lime & Shale	4541	4567'
Lime	4567	4655'
Lime & Chert	4655	4670'
Lime	4670	4840'
Lime & Shale	4840	5022'
Shale	5022	5068'
Lime & Shale	5068	5119'
Lime	5119	5242'
Lime & Chert	5242	5364'
Lime	5364	5652'
Sand & Shale	5652	5700'
Lime	5700	6225 TD

RECEIVED
STATE CORPORATION COMMISSION


JAN 9 1963

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS

COUNTY OF SEDGWICK

I, Don S. Packer, do hereby certify that the foregoing is true and correct to the best of my knowledge and belief.



Don S. Packer

Subscribed and sworn to before me this 6th day of December, 1962.



Helen Y. Langston, Notary Public

My Commission Expires:
March 26, 1963