

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-119-20634-0000

LEASE NAME Meyer E

WELL NUMBER 2

SPOT LOCATION C SW NE NE

SEC. 20 TWP. 33 RGE. 30 ~~W~~ (W)

COUNTY Meade

Date Well Completed 1-6-84

Plugging Commenced 12-17-84

Plugging Completed 12-19-84

LEASE OPERATOR Cities Service Oil & Gas Corporation

ADDRESS 3545 NW 58th St., Okla. City, Okla. 73112

PHONE # (405) 949-4400 OPERATORS LICENSE NO. 5447

Character of Well Dry
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? 2

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation None Depth to top _____ bottom _____ T.D. 6220'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	1540' KB	None
				5-1/2"	5848' KB	2612'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. CIBP set @ 5600' KB. Dumped 2 sx cmt on top of CIBP. Shot off 5 1/2" csg. @ 2612'. Spotted 35 sx Class "H" cement 2612-2512'. Pulled csg. to 1590'. Spotted 50 sx Class "H" 1590-1440'. Pulled csg. to 900' and spotted 35 sx 900-800'. POOH w/csg. and spotted 10 sx Class "H" 40'-4'. Cut off 8-5/8" 4' below surface and welded plate over csg.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Daco, Inc. License No. 38

Address P.O. Drawer 3010, Borger, TX 79008-3010

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

D.G. Oliver, Engineering Manager

(employee of operator) OF STATE CORPORATION COMMISSION

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Nellie L. Oliver

(Address) 3545 NW 58th Street
Oklahoma City, OK 73112

SUBSCRIBED AND SWORN TO before me this 10th day of January, 19 85

Joyce S. Darter
Notary Public

My Commission expires: 6-12-88