

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-119-10072-0000

API NUMBER NA

LEASE NAME Powell

WELL NUMBER #2

SPOT LOCATION C SW NE

SEC. 22 TWP. 33 RGE. 30 (X) or (W)

COUNTY Meade

Date Well Completed 6-4-56

Plugging Commenced 5-12-84

Plugging Completed 5-17-84

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Earl C. Brookover

ADDRESS P.O. Box 917, Garden City, KS 67846

PHONE # (316) 275-9206 OPERATORS LICENSE NO. NA

Character of Well Gas  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dist. #1, 302 W. McArtor, Dodge City

Is ACO-1 filed? No If not, is well log attached? Yes

Producing formation Mississippi Depth to top 5764 bottom 5793 T.D. 5793

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Mississippi</u>	<u>Gas</u>	<u>5764</u>	<u>93</u>	<u>8 5/8"</u>	<u>1532</u>	<u>None</u>
				<u>5 1/2"</u>	<u>5766</u>	<u>2623</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Pump 25 sacks of cement @ 5779 to 5600

Pump 35 sacks of cement @ 1582 to 1482

Put 10 sacks of cement @ 33 to 3

Cut off & cap 8 5/8" 3' below ground level

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address P.O. Box 506, Liberal, KS 67901

RECEIVED  
STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Finney, ss.

JUN 15 1984  
6-15-84

CONSERVATION DIVISION  
Wichita, Kansas


R. W. Lange (employee of operator) or  
(XXXXXX) of above-described well, being first duly sworn on oath, says: That  
I have knowledge of the facts, statements, and matters herein contained and  
the log of the above-described well as filed that the same are true and  
correct, so help me God.

(Signature) [Signature]

(Address) P.O. Box 1034, Garden City

SUBSCRIBED AND SWORN TO before me this 14 day of June, 19 84

My Commission expires: 5-10-86



Mary Anne Larson  
Notary Public

# FILE COPY



ROCKET DRILLING COMPANY, INC. PHONE 3-1277 352 N. BROADWAY WICHITA, KANSAS

James Donoghue  
 P. Powell  
 1/4 SW 1/4 NE 1/4 Section 26-33E-30W  
 Wood County, Kansas

Mr. James Donoghue  
 Denver Club Building  
 Denver, Colorado

Elevations:  
 Spudded: April 30, 1956  
 Rotary Completed: June 1, 1956  
 Contractor: Rocket Drilling Company, Inc.

CASING RECORD

1505' 8-5/8" O.D. 24" seamless casing cemented with 800 sacks cement  
 5793' 5-1/2" O.D. 36" seamless casing cemented with 200 sacks cement.

DRILLER'S LOG

Sand & Clay	0 to 500	Chalky Lime & Shale	3360
Red Bed & Sand	515	Chalky Shale	3335
Sand & Shale	664	Chalky Lime	3580
Red Bed & Anhydrite Streaks	590	Shale & Coal	3753
Anhydrite & Shale	1060	Lime & Shale	3875
Sand & Shale	1115	Lime	4086
Red Bed & Sand	1425	Lime & Shale	4264
Red Bed & Shale	1505	Lime	4300
Shale & Shells	1750	Shale & Lime	4395
Red Bed & Shale	1910	Lime & Shale	4463
Shale & Shells	2305	Lime	4764
Lime & Shale	2420	Chert	4772
Lime & Shale Streaks	2697	Chert & Lime	4821
Lime	2765	Lime	4997
Lime & Shale	2880	Lime & Shale	5105
Lime	3150	Lime	5793 T.D.

STATE OF KANSAS )  
 ) ss  
 COUNTY OF SEDGWICK )

I hereby certify that to the best of my knowledge and belief the foregoing log is true and correct.

ROCKET DRILLING COMPANY, INC.

H. Myrick

Subscribed and sworn to before me, a Notary Public, in and for the County and State aforesaid, this 15th day of June, 1956.

My commission expires:  
 10-25-1956

Notary Public



POCKET DRILLING COMPANY, INC. PHONE 3-1277 352 N. BROADWAY WICHITA, KANSAS

James Donoghue  
42 Powell  
C SW/4 NE/4 Section 22-33S-30W  
Woods County, Kansas

Mr. James Donoghue  
Denver Club Building  
Denver, Colorado

Elevation: \_\_\_\_\_  
Spudded: April 30, 1956  
Rotary Completed: June 4, 1956  
Contractor: Pocket Drilling Company, Inc.

CASING RECORD

1505' 8-5/8" O.D. 24# seamless casing cemented with 800 sacks cement.  
5793' 5-1/2" O.D. 14# seamless casing cemented with 200 sacks cement.

DRILLERS LOG

Sand & Clay	0 to 350	Chalky Lime & Shale	3360
Red Bed & Sand	315	Chalky Shale	3435
Sand & Shale	665	Chalky Lime	3580
Red Bed & Anhydrite Streaks	940	Shale & Chalk	3753
Anhydrite & Shale	1060	Lime & Shale	3875
Sand & Shale	1145	Lime	4086
Red Bed & Sand	1425	Lime & Shale	4260
Red Bed & Shale	1505	Lime	4360
Shale & Shells	1550	Shale & Lime	4395
Red Bed & Shale	1910	Lime & Shale	4483
Shale & Shells	2305	Lime	4764
Lime & Shale	2425	Chert	4772
Lime & Shale Streaks	2497	Chert & Lime	4821
Lime	2765	Lime	4997
Lime & Shale	2980	Lime & Shale	5105
Lime	3190	Lime	5793 T.D.

STATE OF KANSAS )  
COUNTY OF SEDGWICK ) SS

I hereby certify that to the best of my knowledge and belief the foregoing log is true and correct.

POCKET DRILLING COMPANY, INC.

U. H. Myrick  
U. H. Myrick

Subscribed and sworn to before me, a Notary Public, in and for the County and State aforesaid, this 15th day of June, 1956.

My commission expires:  
10/28/1959

Notary Public