

15-077-10186-00-00

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

APR 12 1963
4-12-63
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts.
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Albert Schiffner of Forbes Casing Pulling has this
date requested permission to plug the following described well:

Mr. Schiffner guarantees payment of the plugging fee.

Operator's full Name: Continental Oil Co.

Complete Address: Box 30, Lyons, Kansas

Lease Name: Mathes Well No. # 3

Location: NE SW NE
1650NL 1650EL Sec. 29 Twp. 31 Rge. 7 (E) (W) W

County Harper Total Depth 4720 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Schiffner was instructed to plug the well as follows:

5 1/2" long string plugged back to 4691', cemented with 250
sacks. Perferated from 4667' to 4672'. 237' of 8 5/8"
surface pipe cement circulated. Sand to 4650', cement
with 5 sacks. Fill hole with mud to 200', 10' rock bridge,
cement with 20 sacks. Fill hole to 40', 10' rock bridge,
cement with 10 sacks to base cellar.

Very truly yours,

Archie Elving
Conservation Division Agent