

State of Kansas



## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)RECEIVED  
STATE CORPORATION COMMISSION

AUG 13 1974

CONSERVATION DIVISION  
Wichita, KansasJ. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Wilson of Gulf has this

date requested permission to plug the following described well:

Mr. Wilson guarantees payment of the plugging fee.Operator's full Name: Gulf Oil CorpotationComplete Address: Box 12116, Oklahoma City, OklahomaLease Name: Edna Collingwood Well No. 4Location: C SE NW Sec. 1 Twp. 33 Rge. 30 XX (E) (W)County: Meade Total Depth 5870' Oil Well XGas Well      Input Well      SWD Well      D & A      Lost Hole     Mr. Wilson was instructed to plug the well as follows:8 5/8" to 1564' circulated w/ cement. 5 1/2" to 5870' cemented.Top perforations 5600' Plug bottom w/ 20 sacks cement.Top of cement 5450' Mud 5450' to 1564'Spot 50 sacks cement 1564' to 1400' Mud 1400' to 30'Plug, Hulls & 20 sacks cement 30' to 0'.

Very truly yours,

  
Conservation Division Agent