

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-119-10100-0000

Well was completed on

API NUMBER 9-8-1951

LEASE NAME Novinger

WELL NUMBER 201

660 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 23 TWP. 33S RGE. 30W (~~30E~~) (W)

COUNTY Meade

Date Well Completed 9-8-1951

Plugging Commenced 5-2-88

Plugging Completed 5-4-88

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR OXY USA Inc.

ADDRESS 3545 N.W. 58th Street, Oklahoma City, OK 73112

PHONE# (405) 949-4400 OPERATORS LICENSE NO. 5447

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District 1, Glenn Barlow
 Well was completed on

Is ACO-1 filed? 9-8-1951 If not, is well log attached? yes

Producing Formation Marmaton Depth to Top 5262 Bottom 5275 T.D. 5294

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Marmaton	Oil	5262	5275	13 3/8	670	none
				9 5/8	2698	none
				5 1/2	5293	2737

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
 CIBP @ 5020 w/2 sks.

Pump 50 sks. of cement to plug bottom of 9 5/8, plug from 2720 to 2620.

Pump 50 sks. of cement to spot plug inside of 9 5/8 at bottom of 13 3/8, plug from 690 to 590

Put 20 sks. of cement from 60 to 0 Cut off & cap 9 5/8 3' below ground level

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address Box 506 Liberal, Kansas 67905-0506

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 2 1988

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

CONSERVATION DIVISION
 Wichita, Kansas

Bryan Humphries (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Bryan O. Humphries

(Address) 3545 N.W. 58th Street

Oklahoma City, OK 73112

SUBSCRIBED AND SWORN TO before me this 26th day of May, 19 88

Marsha G. Wilson
 Notary Public

My Commission Expires: 4-1-92