

15-077-19048-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-1

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Harper County, Sec. 13 Twp. 31 Rge. 9 (E) (W)

Location as "NE/CNW/SE/SW" or footage from lines SW SE NE  
Lease Owner Drillers Production Company  
Lease Name Grabs A#3 Well No. \_\_\_\_\_  
Office Address Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 7/11/74 19\_\_\_\_  
Plugging completed 7/17/74 19\_\_\_\_  
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? yes

Name of Conservation Agent who supervised plugging of this well Biberstein  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4433 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	254	none
				5 1/2"	4423	3299'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked bottom, pushed plug to 4420' and sanded back to 4400' and dumped 5 sacks cement, top cement 4365'. Loaded hole, shot pipe at 3732', 3630', 3467', 3369', pulled 100 joints. Set 10' rock bridge at 325' and dumped 6 yards ready mix. Dumped 5 more yards ready mix.

PLUGGING COMPLETE.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 29 1974  
7-29-74  
CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.  
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE  
NOEL J. KNIGHT ss.  
(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight  
Chase, Kansas  
(Address)

Subscribed and Sworn to before me this 18th day of July 1974

MARGARET MELCHER  
NOTARY PUBLIC  
Rice County, Kansas  
My Commission Expires  
Feb. 15, 1975

Margaret Melcher  
Notary Public.



1974

1974

1974

1974

1974

1974



DRILLERS PRODUCTION CO., Inc.  
#3 Grabs  
SW SE NE, Sec. 13-31S-9W  
Harper County, Kansas

Drilled by: Beardmore Drilling Co.  
Drilling Commenced: 5-8-55  
Drilling Completed: 5-19-55

Elevations: KB 1643  
DF 1640  
Gr 1637

Casing Record:

Set 254' of 8 5/8" with 175 sacks. Cement circulated. 5-8-55  
5 1/2" set at 4423' with 100 sacks. 5-19-55

<u>FORMATIONS</u>	<u>DEPTH</u>
Cellar	5
Sand	85
R. Rock and Shale	254
R. Rock and Shale	550
Shale	1050
Shale and Shells	1300
Lime and Shale	2025
Lime and Shale	2755
Lime and Shale	3370
Lime and Shale	3745
Lime and Shale	3865
Lime	3935
Lime and Shale	3983
Lime and Shale	4055
Lime	4100
Lime and Shale	4180
Lime	4230
Lime and Shale	4355
Lime	4407
Lime and Chert	4418
Lime	4433
Rotary Total Depth	4433

TOPS:

Mississippi 4403  
Lansing 3641

DST #1 - 4406-4418: Open 1 hour. Shut in 20 minutes. Gas to surface in 2 minutes. 768 MCFG. Recover 35' free oil, 90' heavily oil and gas cut mud. BHP 1515, IF 70, FF 95.

CO 4433 1 BDPH + 1% wtr.  
Frac Flow 24 BFPH/3 hr 26% wtr.  
I.P. 348 BOPD + 10% wtr + Est 1,500,000 CFG

STATE OF KANSAS }  
COUNTY OF SEDGWICK) ss

I, the undersigned, being duly sworn on oath state that the above and within statement is a true and correct record and log of the well drilled on the location above-described, to the best of my knowledge and belief.

*[Signature]*

Subscribed and sworn to before me this 27th day of May, 1955.

*Leonard P. Tolle*  
Notary Public

My Commission Expires:  
January 28, 1956