

State of Kansas



## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)RECEIVED  
STATE CORPORATION COMMISSION

FEB 19 1974

CONSERVATION DIVISION  
Wichita, KansasJ. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Sargent of McAdams has this  
date requested permission to plug the following described well:Mr. Sargent guarantees payment of the plugging fee.Operator's full Name: McAdams Pipe & Supply CompanyComplete Address: Box 960, Bristow, OklahomaLease Name: Holmes Well No. 3Location: C SE NW Sec. 2 Twp. 33 Rge. 30 (E)(W)County: Meade Total Depth 5850' Oil Well XGas Well      Input Well      SWD Well      D & A      Lost Hole     Mr. Sargent was instructed to plug the well as follows:9 5/8" to 1589' circulated w/ cement. 5 1/2" to 5835' cemented.Top perforations 5659' Plug, Bottom w/ 20 sacks cement.Top of cement 5450' Mud 5450' to 900'Spot 35 sacks cement 900' to 800' Mud 800' to 45'Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

  
Conservation Division Agent