

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 5 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Sargent of McAdams has this

date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: McAdams Pipe & Supply Co.

Complete Address: Box 960, Bristow, Oklahoma

Lease Name: Holmes Well No. 7

Location: C NW NE Sec. 2 Twp. 33 Rge. 30 ^{XX}(E)(W)

County: Meade Total Depth 5890' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Sargent was instructed to plug the well as follows:

3 5/8" to 1636' circulated w/ cement. 5 1/2" to 5887' cemented,

Top perforations 5649' Plug bottom w/ 20 sacks cement

Top of cement 5540' Mud 5540' to 1000'

Spotted 35 sacks cement 1000' to 900' Mud 900' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,


Conservation Division Agent