

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAR 5 1963
03-05-63
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name W.J. Coppinger

Complete Address: 717 Union Natl. Bldg. Wichita, Kansas

Lease Name Meyer Well No. # 1

Location C NE NW Sec. 20 Twp. 33 Rge. 30 (E) / (W)

County Meade Total Depth 6225'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Forbes Casing Pulling Co.

Address: Great Bend, Kansas License No. 49

Operation Completed: Hour 10 PM Day 1 Month 3 Year 63

The Above well was plugged as follows:

8 5/8" 1451' Circulated w/cement. 4 1/2" 5800' Cemented.

Plug back to 5766' Top perforations 5696 1/2'

Plug bottom 5766' to 5650' w/sand--5 sax.cement.

Mud 5650' to 760' 10' rock bridge 760' to 750'

35 sax.cement 750' to 650' Mud 650' to 50'

10' rodk bridge 50' to 40' 15 sax.cement 40' to surface.

Weld cap on surface. Company Pump. Pulled 5070' 4 1/2" pipe.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 3/5/63

INV. NO. 6680-W

Signed: [Signature]
Well Plugging Supervisor