

KANSAS

10

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JAN 26 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Earl C. Brookover

Complete Address 211 N. Main, Garden City, Kansas 67846

Lease Name Powell Well No. 1

Location C SE NE Sec. 22 Twp. 33 Rge. 30 (E) (W)

County Meade Total Depth 5805'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A X

Other well as hereafter indicated None

Plugging Contractor Knight Casing Pulling Co.

Address Box 405, Chase, Kansas License No. 624

Operation Completed: Hour 5:00PM Day 21 Month 1 Year 1970

The above well was plugged as follows:

8 5/8" to 1607' circulated w/ cement. 5 1/2" to 5787' cemented.

Top perforations 5266' Plug bottom w/ 40 sacks cement.

Top of cement 4900' Mud 4900' to 600'

Spotted 35 sacks cement 600' to 500' Mud 500' to 45'

Plug. Hulls & 15 sacks cement 45' to 0'.

Halliburton Cementing Co. Plugged bottom.

Pulled 2800' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: *Edgar E. Jones*
Well Plugging Supervisor

INVOICED

DATE 1/26/70
INV. NO. 1302-4