

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
APR 3 - 1972
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Cities Service Oil Co.

Complete Address Box 1098, Liberal, Kansas 67901

Lease Name Yake Well No. 101

Location SE SE Sec. 22 Twp. 33 Rge. 30 ~~(S)~~ (W)

County Meade Total Depth 5868'

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated None

Plugging Contractor Toland & Johnston

Address Oklahoma City, Oklahoma License No. 539

Operation Completed: Hour 4:30 PM Day 28 Month 3 Year 1972

The above well was plugged as follows:

12 3/4" to 606' circulated w/ cement. 8 5/8" to 1765' cemented.

5 1/2" to 5868' cemented. Top perforations 5276'

Plug bottom w/ 20 sacks cement 5276' Top of cement 5100'

Mud 5100' to 1700' Spotted 35 sacks cement 1700' to 1600'

Mud 1600' to 40' Plug, Halls, 10 sacks cement 40' to 0'.

Pulled 2558' of 5 1/2" casing. Company Pump

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edgar J. Evers
Well Plugging Supervisor

DATE 4-3-72

INV. NO. 5467-W